Sarah Groom

From: David Warland <info@silverstainedglass.com>
Sent: 12 January 2022 13:58
To: Sarah Groom
Subject: Re: South Avenue Cemetery Chapel Stained Glass Windows

Follow Up Flag: Follow up
Flag Status: Flagged

Dear Sarah,

As you know David visited today and our advice is to remove and rebuild 3 panels and carry out one insitu repair- please see our quote below-
REBUILD QUOTE
To remove the panel/s 3 @ 415mm x 910mm and board up/glaze the space- carefully transport to the workshop, take apart- clean the glass. Re-lead using lead to match the existing profile and original glass- replacing broken or cracked pieces with best match possible, Cement to make waterproof and stabilise, then refit we can use the original saddle bar or replace with new-

Remove- £270 plus vat

Strip and rebuild- £173 plus vat per panel- £519 plus vat

Refit- £270 plus vat

Total - £1059 plus vat

New saddle bars would be £15 plus vat each if needed.

INSITU REPAIR QUOTE

We would carefully fold back the lead- before removing the broken panes of glass- we would then hand cut new pieces in best match possible glass which we would carefully insert, then gently fold back the lead and secure in place- with black putty- to make stable and waterproof.

£65 Plus vat

Total for all work- £1124 plus vat (excluding bars)

Please let me know if you would like to proceed.

Many thanks

Lisa Taylor

Tel-01273 857223
Mon-Fri 9:30 to 14:30
www.silverstainedglass.com